

Project: PAW Berwick to Nescopeck

Location: Berwick, PA

Project Details:

Aaron Enterprises, Inc. was contracted to install 1,700 LF of 14" HDPE by HDD under the Susquehanna River at a depth of 130' below the river bottom. The pilot hole was completed utilizing a gyro intersect method with a drill rig on both sides of the river. 36" conductor casing was installed down to the rock on each side of the river through glacial till. A 1,400 LF slip line of the existing water main across the river was also completed on the project by AEI.

Final Product: 14" HDPE

Geology: Sandstone/shale/limestone



Project Profile

Horizontal Directional Drilling

Completion Date

June 2021

Installation Methods:

Horizontal Directional Drilling
Pipe Ramming

Markets Served:

Sewer & Water

Owner:

PA American Water

Engineer:

Gannett Fleming

Contractor:

Pioneer Construction

For More Information:

Paul Grove – Vice President - (717) 854-2641 ext. 234
Reference Job # 2041346