

Project: CPS Loop 610 & I-10

Location: San Antonio, TX

Project Details:

Aaron Enterprises, Inc. was contracted to complete 4 auger bores in San Antonio, TX to relocate a 16" gas main for an upcoming highway project. 450 LF of boring was completed- ranged from 80' to 175'. Pipe was installed in hard limestone with known karst features using a 16" hammer. Voids were encountered and grouting of the annular area was required to complete bore to highway specifications. Project was completed on a 24/7 basis due to the need for closures of highway on/off ramps.

Final Product: 16" Steel Gas Main

Geology: Karst Limestone

Project Profile

Auger Boring

Completion Date

February 2022

Installation Methods:

Auger Boring
Grouting

Markets Served:

Transportation
Oil & Gas



Owner:

CPS Energy

Engineer:

CEC

Contractor:

Mears

For More Information:

John Seibert, E.I.T – Director of Oil & Gas - (717) 854-2641 ext. 240
Reference Job # 2132326