



300 Cloverleaf Road, York, PA 17406
www.aaronenterprises.com
717-854-2641

Project: 20 MW Capacity Enhancement Phase 1 & 2

Location: Philadelphia Navy Yard, PA

Project Details:

Aaron Enterprises, Inc. was contracted to complete a design build HDD across a channel at the Navy Yard in Philadelphia. The crossing length was 1100 LF to install a 16" HDPE bundle. 36" conductor casing and soil grouting was employed to contain fluids on rig side. AEI was contracted two years later to complete the second phase which consisted of an additional 3300 LF of 24" HDPE bundle install on three separate crossings by HDD.

Final Product: Phase 1: (4) 6" HDPE bundle, Phase 2: (8) 6" HDPE bundle

Geology: Low blow count sand



Project Profile

Engineering Services

Completion Date

Phase 1- February 2019

Phase 2- October 2021

Installation Methods:

Horizontal Directional Drilling

Pipe Ramming

Soil Stabilization

Grouting

Engineering Services

Markets Served:

Electric



Owner:

US Navy

Engineer:

Burns Engineering Inc.,
David Mason Associates, & Pennoni

Contractor:

JPC Group, Inc.
Miller Bros. Construction, Inc.

For More Information:

Paul Grove – Vice President - (717) 854-2641 ext.234
Reference Job # 1824546/2031346

