

Navy Yard 20MW HDD

Philadelphia, PA

Project: **Location:** 

**Project Details:** 

control throughout the project.

300 Cloverleaf Road York, PA 17406 Office: (717) 854-2641 Fax: (717) 854-2310 www.aaronenterprises.com







## Project Profile Horizontal Directional Drilling

**Completion Date** August 2025

## **Installation Methods:**

Horizontal Directional Drilling Pipe Ramming Soil Stabilization Grouting

> **Markets Served:** Electric

**Engineering Services** 

# **Final Product:** (8) 6" HDPE Bundle Geology: Fill, Sands, Silts

scope of work included the successful installation of 3,032 linear feet of eight (8) 6-inch HDPE conduits.









Aaron Enterprises was contracted to perform three horizontal directional drills (HDDs) at the historic Navy Yard in Philadelphia. The

To ensure containment of drilling fluids and maintain ground stability, each HDD entry point was reinforced with 42-inch conductor casing and treated using soil grouting techniques. This approach minimized environmental impact and ensured precise bore path

> **Owner:** Dominion Energy Services, Inc.

**Engineer:** Burns & McDonnell

**Contractor: RCR Electrical Contractors** 

## For More Information:

Rees Roberts - Project Manager - (717) 854-2641 ext. 229 Reference Job # 2432046

